


FRONT VIEW



BY ACCESSIBILITY PROFESSIONALS

SPECIFICATION SHEET APT_XST6032TSADAR

Finished surface shall be of a sanitary grade Acryl^{IX}™ applied acrylic. The base shall be attached to the sump in such manner to form an integral part with an inner and outer coating of polyester resin. Unit construction shall be of a molded reinforced fiberglass with a 15% minimum fiberglass content.


The unit shall have outside dimensions of 60" x 33" x 77".
The unit shall meet CSA B45.5, HUD-UM73, and UPC.

HANDED BY THE VALVE


The enclosure shall be equipped with the following accessories:

- 1) Bare unit,
- 2) Tile finish,
- 3) Diamond accents,
- 4) Molded low shelf.

SIDE VIEW



TOP VIEW



NOTE: CODE GRAB BARS AND FOLD UP SEAT ARE REQUIRED FOR ADA, ANSI A117.1, AND MAS CODE COMPLIANCE.

THIS UNIT FEATURES THE OUTSIDE DIMENSION OF 60" OF OVERALL WIDTH. THIS DOES NOT ALLOW FOR FULL ENCLOSURE OF THE BOLTS AND NUTS USED TO SECURE THE BARS AND SEAT IN PLACE. THE BOLT AND NUT COMBINATION SHOULD NOT PROTRUDE MORE THAN 3/4" ON EITHER SIDE OF THE TUB SHOWER WALLS. THIS MAY REQUIRE THE NEED TO NOTCH STUDS TO ALLOW BOLT CLEARANCE FOR A DRYWALL ENCLOSED FIRE WALL INSTALLATION. ADJUSTMENT OF THE WALL BOARD MAY BE NECESSARY TO PROVIDE CLEARANCE OF THE BOLT(S) WHILE MAINTAINING THE INTEGRITY OF THE DRYWALL ENCLOSED FIRE WALL ENCLOSURE.

NOTE: THIS UNIT WILL NOT ACCEPT A DOOR.

Job Name	Approved By Print Name		Date	APT_XST6032TSADAR	
Project No	Approved By Signature				
FreedomShowers.com 1-877-947-7769	Architect			Drawing No. XST 6032 TS Bare	
	Engineer			Date Issued, 4-3-12	Drawing Rev. 3-7-24
	Rep			Material. Acryl ^{IX} ™ Applied Acrylic	
	Wholesaler			Color:	
	Comments				Dimensions are in inches. Due to the nature of the materials dimensions may vary ± 1/2"